

| Lift and Crane | | |
|----------------------------------|--|--|
| Plant/Equipment Type | Frequency | Legislation |
| Forklift Trucks | 12 months (6 months if person lifted) | SI No. 299 of 2007 (PT2-Ch3) |
| Tower Crane/Self Erectors | 12 months | SI No. 299 of 2007 (PT2-Ch3) |
| General cranes | 12 months | SI No. 299 of 2007 (PT2-Ch3) |
| Passenger/Goods Lifts | 6 months | SI No. 299 of 2007 (PT2-Ch3) |
| Lifting Tackle/Accessories | 6 months | SI No. 299 of 2007 (PT2-Ch3) |
| Lifting machines | 12 months | SI No. 299 of 2007 (PT2-Ch3) |
| Cranes | 12 months | SI No. 299 of 2007 (PT2-Ch3) |
| Lorry Mounted Cranes | 12 months | SI No. 299 of 2007 (PT2-Ch3) |
| Mobile Cranes | 12 months | SI No. 299 of 2007 (PT2-Ch3) |
| Vehicle Lifting Tables | 12 months | SI No. 299 of 2007 (PT2-Ch3) |
| High Lift Pallet Trucks/Stackers | 12 months | SI No. 299 of 2007 (PT2-Ch3) |
| Vehicle Tail Lifts | 12 months | SI No. 299 of 2007 (PT2-Ch3) |
| Teleporters | 12 months (6 months if person lifted) | SI No. 299 of 2007 (PT2-Ch3) |
| Mobile Elevated Work Platforms | 6 months | SI No. 299 of 2007 (PT2-Ch3) |
| Window Cleaning Platforms | 6 months | SI No. 299 of 2007 (PT2-Ch3) |
| Dock Levelers | 12 months | SI No. 299 of 2007 (Section 30) |
| Pallet Trucks | 12 months | SI No. 299 of 2007 (Section 30) |
| PPE Body Harness and Lanyards | 6 months | SI No. 299 of 2007 (Section 30) |
| Escalators/Travelators | 12 months | SI No. 299 of 2007 (Section 30) |
| Excavator | 12 months | SI No. 299 of 2007 (Section 30) or (PT2-Ch3) if used as crane |
| Dumper trucks | 12 months | SI No. 299 of 2007 (Section 30) |
| Loading Shovels | 12 months | SI No. 299 of 2007 (Section 30) |
| Hydraulic Jacks | 12 months | SI No. 299 of 2007 (Section 30) |

| Pressure Plant | | |
|--|----------------------|--|
| Plant/Equipment Type | Frequency | |
| Air Receivers | 26 months | SI No.445 of 2012 |
| Pressurised Tanks | 26 months | SI No.445 of 2012 |
| Autoclaves | 26 months | SI No.445 of 2012 |
| Autoclaves -Steam Generating | 14 months | SI No.445 of 2012 |
| Hot Water/Heating Boilers <110C | 12 months | SI No. 299 of 2007 (Section 30) |
| Hot Water/Heating Boilers >110C | 14 months | SI No.445 of 2012 |
| Steam Boilers | 14 months | SI No.445 of 2012 |
| Blowdown Vessel | 26 months | SI No.445 of 2012 |
| Café Boilers | 14 months | SI No.445 of 2012 |
| Calorifiers | 26 months | SI No.445 of 2012 |
| Jacketed Reactor Vessel | 26 months | SI No.445 of 2012 |
| Jacketed Process Vessels | 26 months | SI No.445 of 2012 |
| Steam Vessels | 26 months | SI No.445 of 2012 |
| Process Vessels | 26 months | SI No.445 of 2012 |
| Pressurisation Units | 26 months | SI No. 299 of 2007 (Section 30) |
| Refridgeration/Air Conditioning Units (> 25kW) | 26 months | General Apps (SI No.445 of 2012) |
| Refridgeration/Air Conditioning Units (>25kW) | 26 months | SI No. 299 of 2007 (Section 30) |
| LPG Storage Tanks | 12 months as per WSE | SI201 of 1990 Storage of LPG, using UKLPG Code of Practices and ISEN12819 2009 |
| LPG Road Tankers | 12 months as per WSE | 2010 TPED Transportable Pressure Equipment Directive SI 349 of 2011 |

| Electrical | | |
|--|----------------------------------|--|
| Plant/Equipment Type | Frequency | Legislation |
| Motors | Recommended as 12 months | SI No. 299 of 2007 (Part 3) |
| Transformers | Recommended as 12 months | SI No. 299 of 2007 (Part 3) |
| Supply Panels | Recommended as 12 months | SI No. 299 of 2007 (Part 3) |
| Fixed Electrical Installations | Recommended as 12 months | SI No. 299 of 2007 (Part 3) |
| Generators | Recommended as 12 months | SI No. 299 of 2007 (Part 3) |
| Portable Power Tools | Recommended as 12 months | SI No. 299 of 2007 (Part 3/Section 30) |
| Hazardous Area Electrical Installation | Various depending on Legislation | SI No. 299 of 2007 (Part 8) |

| Work Equipment | | |
|--------------------------------------|-----------|---------------------------------|
| Plant/Equipment Type | Frequency | |
| Roof Fall Protection System | 12 months | SI No. 299 of 2007 (Section 30) |
| Road Retexturing Vehicles/ Machinery | 12 months | SI No. 299 of 2007 (Section 30) |
| Rock Crusher | 12 months | SI No. 299 of 2007 (Section 30) |
| Power Screen | 12 months | SI No. 299 of 2007 (Section 30) |
| Combined Heat and Power Plant | 12 months | SI No. 299 of 2007 (Section 30) |
| Hydraulic Compactor | 12 months | SI No. 299 of 2007 (Section 30) |
| Stone Drilling Rig | 12 months | SI No. 299 of 2007 (Section 30) |
| Chipper | 12 months | SI No. 299 of 2007 (Section 30) |
| Roller | 12 months | SI No. 299 of 2007 (Section 30) |
| Loader/Backhoe | 12 months | SI No. 299 of 2007 (Section 30) |
| Pile Driver | 12 months | SI No. 299 of 2007 (Section 30) |
| Timber Harvester | 12 months | SI No. 299 of 2007 (Section 30) |
| Block Layer | 12 months | SI No. 299 of 2007 (Section 30) |
| Block Strapping Machine | 12 months | SI No. 299 of 2007 (Section 30) |
| Ladder | 12 months | SI No. 299 of 2007 (Section 30) |
| Mobile Steps | 12 months | SI No. 299 of 2007 (Section 30) |
| Working Platform | 12 months | SI No. 299 of 2007 (Section 30) |
| Palletising Machine | 12 months | SI No. 299 of 2007 (Section 30) |
| Pallet Invertor | 12 months | SI No. 299 of 2007 (Section 30) |
| Tractors | 12 months | SI No. 299 of 2007 (Section 30) |
| Agricultural Machinery | 12 months | SI No. 299 of 2007 (Section 30) |
| Pallet Racking | 12 months | SI No. 299 of 2007 (Section 30) |

SI No. 299 - Safety, Health and Welfare at Work (General Application) Regulations 2007 (As Amended).

The contents of this guide are for general information purposes only. Whilst Aviva endeavours to ensure that the information on this site is correct, no warranty, express or implied, is given as to its accuracy and Aviva does not accept any liability for error or omission. Visit: <http://www.aviva.ie/business-insurance/products/engineering-services/> for further details.